


All Chimney Stacks, Cappings and  
Pots to be restored and retained.



Existing Slate roof covering and capping to be removed and preserved to facilitate replacement or repair of defective structural roof elements, repair or replacement of associated flashings or coverings, preservation or restoration works to walls. Preserved slating and capping to be refitted in traditional manner to match existing upon completion of structural works.

All existing Windows to be replaced with traditional Timber Sash Windows, reveals, heads and cills to be restored as per original building

Existing Rain Water Goods to be made good and to retained.

Existing Timber front door to be restored to original form and retained

Removable access ramp to be provided on request to facilitate assisted access for mobility challenged visitors via existing front door. Permanent D.A.C to be provided via rear entrance.

**Note 1** - External lighting to be located on the external of the existing building shall be designed in line with heritage guidelines and approved by Heritage officer or Conservation Architect.

**Note 2** - External signage to be located on the existing elevations shall be designed in line with heritage guidelines and approved by Heritage Officer or Conservation Architect.

Notes:  
Demolition work is shown **RED**  
New Construction is shown **GREEN**

**Elevation 1** Datum : 44.00m

• THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER ARCHITECTURAL AND ENGINEERING DRAWINGS AND ALL OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.

• DO NOT SCALE THIS DRAWING USE FIGURED DIMENSIONS ONLY.

• NO PART OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR STORED IN ANY RETRIEVAL SYSTEM OF ANY NATURE WITHOUT THE WRITTEN PERMISSION OF LONGFORD COUNTY COUNCIL AS COPYRIGHT HOLDER EXCEPT AS AGREED FOR USE ON THE PROJECT FOR WHICH THE DOCUMENT WAS ORIGINALLY ISSUED.

C:\Users\mcassidy\AppData\Local\Autodesk\AutoCAD LT 2024\R30\enu\Template\LCC Drawing Template MC - A1 & A3.dwt

Rev. No.	Date	Revision Notes	Dm. by	Chkd. by



**Copyright Acknowledgements**  
CYAL50380265© Tailte Éireann.

Unauthorised reproduction infringes  
Tailte Éireann copyright.

KEY:  
SITE BOUNDARY —  
OWNERSHIP BOUNDARY —

**COMHAIRLE CHONTAE LONGFOIRT**

LONGFORD COUNTY COUNCIL

**GREAT WATER STREET  
LONGFORD**  
Tel. (043) 46231

Client :	Longford County Council
Project :	Former Longford Post Office Building Re-development
Title :	Proposed Elevation 01
Drawing No: 011	Revision: 00
Scale: 1:100 @ A3	Date: 19/06/2025
Drawn by: M.Cassidy	Checked: C.R
Status: Part 8	Approved: P.N